

**TOWN OF ASHLAND, NEW HAMPSHIRE
SANBORN ROAD CONSTRUCTION PROJECT
BID SPECIFICATIONS INCLUDE -**

1. Clean ditches and cut back slopes
2. Remove ledge in ditch line
3. Replace four (4) culverts: two (2) – 15" X 40', one (1) – 18" X 40', one (1) – 18" X 50' – Town will supply culvert
4. Install three (3) drop inlets: one at 15" X 40', one at 18" X 40', one at 18" X 50' – Town will supply drop inlets
5. Install flared end sections on outlet end of culvert pipe
6. Build stone culvert headers
7. All paved driveway entrances will be saw cut five (5) feet in depth, eight (8) feet in width, and pavement removed
8. Reclaim approximately 18 X 2200 feet of pavement at a depth of 12" with a reclaiming machine
9. Grade reclaimed material and compact with a minimum 10 ton vibratory roller
10. Add 6" of 1" ledge pak. Grade and compact with a minimum 10 ton vibratory roller
11. Install stone in ditches in required areas
12. All disturbed slopes will be loamed and seeded
13. Install one (1) foot of shoulder gravel after paving
14. Contractor will be responsible for signage and traffic control
15. Before any construction begins, Dig Safe must be notified and all utilities sign off for all line locations
16. Paving of road to be conducted at later date under separate bid and contract
17. Scope of the project will be addressed at pre-bid meeting and will include any recommended changes

Mandatory Pre-Bid Meeting - Wednesday May 5, 2010 at 9 AM on site
Sealed bid deadline – Wednesday May 12, 2010 at 4 PM

Town of Ashland Highway Department
PO Box 517
Ashland, NH 03217
603-968-3166